



Springlake-Earth Independent School District

P.O. Box 130 Earth, TX 79031-0130

Phone: (806) 257-3310

Fax: (806) 257-3927

www.springlake-earth.org



Home of the Wolverines

Denver Crum – Superintendent

Cindy Furr – Principal

Bub McIver--Principal

RFP E-Rate 22-23

Qty	Description
3	ICX7250-24P-2X10G 24-port 1 GbE switch bundle with 2x1GbE/10GbE + 6x1GbE SFP+ (upgradeable to 10GbE) uplink/stacking ports upgrade Locations: High School IDF, Elementary IDF, Admin IDF, Ag rack, Band Hall rack, Field House rack. Includes VLAN
15	L2+L3 Features and POE+ 24 Port Switches to replace existing DELL N2048 Switches: ICX7150-48PF-4X10GR SPA/DR: RKS-0361 ER0227723 ICX 7150 Switch, 48x 10/100/1000 PoE+ ports, 2x 1G RJ45 uplink-ports, 4x 10G SFP+ uplink-ports 740W PoE budget, L3 features (OSPF, VRRP, PIM, PBR). Note: These are designed to be managed with the Ruckus controller
15	Installation - Basic Setup, configuration, data migration and prep for school network and imaging.
2	10G-SFPP-TWX-P-0508 10GbE Direct Attach SFP+ to SFP+ Passive copper cable, 5 m, 8-pack
1	VLAN of above Installed SEISD Network Switches



Springlake-Earth Independent School District

P.O. Box 130 Earth, TX 79031-0130

Phone: (806) 257-3310

Fax: (806) 257-3927

www.springlake-earth.org



Home of the Wolverines

Denver Crum – Superintendent

Cindy Furr – Principal

Bub McIver--Principal

1

Fortinet Fortigate Router-Firewall FG-100F-BDL-950-36. 22 x GE RJ45 ports (including 2 x WAN ports, 1 x DMZ port, 1 x Mgmt port, 2 x HA ports, 16 x switch ports with 4 SFP port shared media), 4 SFP ports, 2x 10G SFP+ FortiLinks, dual power supplies redundancy., Hardware plus 24x7 FortiCare and FortiGuard Unified Threat Protection (UTP), 3Yr Bundle, 24x7 Comprehensive Support, Advanced Hardware Replacement (NBD), Firmware and General Upgrades, UTP Services Bundle (IPS, AV, Botnet IP/Domain, Mobile Malware, FortiGate Cloud Sandbox including Virus Outbreak and Content Disarm & Reconstruct, Application Control, [REDACTED] Antispam Service) plus term of contract

1

Basic Installation of Item 10 above including removal of existing router, placement in the rack, and basic router connectivity to the ISP. Includes firewall, [REDACTED]